

BYATARAYANAPURA ZONE

[illegible]

3	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm.KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.0 back filling the pot hole with bituminous material as per clause 500.4 compacting traimming and finishing the surface to form a smooth continuous surface all as per clause 3004.2 complete as per specifications MORTH Specification (Page No. 247/ltn No.35.5) PWD SR 2015-16						Sqm		
	Dasarahalli main Road Cross Roads		30	3.50	1.20		126.00		
	Bhuvaneshawarinagara Main Road		40	3.00	1.20		144.00		
	Cross Roads		30	3.50	1.10		115.50		
	Cauvery Layotu		30	3.50	1.10		115.50		
	Mariyannapalaya		26	3.20	1.75		145.60		
	maruthi layout		20	3.50	1.75		122.50		
							769.10	370.44	284905.00
		Basic Rate	343.00						
		Area Weightage @ 8%	27.44						
		Total	370.44						
									355.00
4	Miscellaneous Expenses								
								Total	500000.00
Rupees Five Lakh(s) Only									

CERTIFICATE

- 1 The work spot has been inspected and the work is found necessary.
- 2 This estimate is prepared as per C.S.R. of 2015-16
- 3 The provisions were made in this estimate are necessary and adequate.
- 4 This works come under B.B.M.P. limits.

Assistant Engineer

Executive Engineer

Bruhat Bangalore Mahanagara Palike
Byatarayanapura Division

Assistant Executive Engineer
Byatarayanapura Sub Division
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು-24

ADMINISTRATIVE APPROVAL

Accorded For Rs. Five lakhs only
Head of A/c. P-1771/15-16
Div. Ref. No. 169 Date 14-12-2015

AE

EE(BTP)

TECHNICAL SANCTION

Accorded For Rs. Five lakhs only
Head of A/c. P-1771/15-16
Div. Ref. No. 178 Date 14-12-2015

AE

EE(BTP)